




Status of the Daya Bay Reactor Neutrino Experiment

HE Miao, IHEP, Beijing, China

On behalf of the Daya Bay Collaboration

DBD11, 14th~17th Nov., Osaka, Japan



Goal of Daya Bay


- Determine θ_{13} : Last unknown mixing angle, sensitivity in $\sin^2(2\theta_{13}) < 0.01$
- Reactor short baseline disappearance experiment

$$P(\bar{\nu}_e \rightarrow \bar{\nu}_e) \simeq 1 - \sin^2(2\theta_{13}) \sin^2(1.27\Delta m_{32}^2 L/E)$$


An unambiguous measurement of θ_{13} , no interference with CP violation phase or matter effects

- Recent knowledge of θ_{13}



T2K:PRL 107,
041801 (2011)



MINOS: PRL 107,
181802 (2011)




Double Chooz:
H. De Kerret, LowNu11




Fogli et al., arXiv:1106.6028

Global evidence for $\theta_{13} > 0$



Daya Bay Collaboration

Political Map of the World, June 1999



Europe (3)

- JINR, Dubna, Russia
- Kurchatov Institute, Russia
- Charles University, Czech Republic

Asia (20)

- IHEP, Beijing Normal Univ., Chengdu Univ. of Sci. and Tech., CGNPG, CIAE, Dongguan Polytech. Univ., Nanjing Univ., Nankai Univ., NCEPU, Shandong Univ., Shanghai Jiao tong Univ., Shenzhen Univ., Tsinghua Univ., USTC, Zhongshan Univ., Univ. of Hong Kong, Chinese Univ. of Hong Kong, National Taiwan Univ., National Chiao Tung Univ., National United Univ.

North America (16)

- BNL, Caltech, LBNL, Iowa State Univ., Illinois Inst. Tech., Princeton, RPI, UC-Berkeley, UCLA, Univ. of Cincinnati, Univ. of Houston, Univ. of Wisconsin, William & Marry, Virginia Tech., Univ. of Illinois-Urbana-Champaign, Siena


~250 Collaborators

Experiment site and nuclear power plant

- Very powerful nuclear power plant:
 - Daya Bay: 2 X 2.9GW
 - Ling Ao I: 2 X 2.9GW
 - Ling Ao II: 2 X 2.9GW (already in operation)
- Total power: ~17.4 GW




Southern
China



Ling Ao II NPP

Ling Ao NPP



Daya Bay NPP

Detector layout

4 x 20 tons target mass at far site

Far site (Hall 3)
1615 m from Ling Ao
1985 m from Daya
Overburden: 350 m

2 x 20 tons target mass at each near site

Ling Ao Near site (Hall 2)
481 m from Ling Ao
526 m from Ling Ao II
Overburden: 112 m

Daya Bay Near site (Hall 1)
363 m from Daya Bay
Overburden: 98 m

Water hall

Liquid Scintillator hall

entrance

SAB




Construction tunnel

Ling Ao-II NPP
2x2.9 GW


Ling Ao NPP, 2x2.9 GW

Daya Bay NPP, 2x2.9 GW

Total tunnel length ~ 3000 m






Experiment hall



Antineutrino Detectors (AD)

- 8 identical modules at 3 sites
- Each module consists of 3 cylindrical zones
 - inner acrylic vessel (IAV), 20ton Gd-LS, *antineutrino target*
 - outer acrylic vessel (OAV), 20ton LS, containing escaped gammas from IAV
 - stainless steel vessel (SSV), 40ton mineral oil, radiation shield
- 192 8" PMTs/module
- Reflectors on the top and bottom
- Expected antineutrino signal from MC




Muon system

- Combined measurement of muon by the Water Cherenkov detector and the Resistive Plate Chambers (RPC)
- High efficiency: $\epsilon > (99.5 \pm 0.25)\%$


Water Cherenkov (Water Pool)

- Provide at least 2.5m shield against radioactivity and neutron
- Divided into two parts, forming two independent detectors



RPC

- 54 modules at near sites and 81 modules at far site
- 2 extra telescope modules at each site
- 4 layers with X or Y strip in each module





Detector construction and installation

AD Prototype




[Nucl. Instrum. Meth. A Volume 602, 489-493 \(2009\)](#)

- **Motivation**



- Validate the design principle
- Test technical details of tanks
- Test Gd-LS
- Test calibration source

- **Achievements**

- Energy response & MC Comparison
- Reconstruction algorithm
- Neutron response
- Effects of reflectors
- Gd-LS property and stability



AD installation




AD Installation in the clean room of the Surface Assembly Building (SAB)



AD dry run

- An integration test for the first pair of ADs before filling with liquid
 - AD + electronics + DAQ+ slow control + data storage + network transfer + database + online/offline analysis




All PMTs are working


Functionally identical ADs!



Number of fired PMTs by muon



Charge ratio for each PMT ring




Gd-doped liquid scintillator


[Nucl. Instrum. Meth. A Volume 578, 329-339 \(2007\)](#)

[Nucl. Instrum. Meth. A Volume 584, 238-243 \(2008\)](#)

- Daya Bay uses 185 ton 0.1% Gd-doped LS: Gd-TMHA + LAB + 3g/L PPO + 15mg/L bis-MSB
- Stability of the Gd-LS has been tested with a prototype detector since Jan. 2007
- All Gd-LS produced in 50 4-ton batches and mixed in one reservoir on-site, to ensure the samples uniform for all ADs.



- 1st batch of 4-ton Gd-LS in Oct. 2010
- Mixing equipment in the underground hall
- Monitoring of Gd-LS in underground storage tanks



GDLS/LS filling


- Requirement: precise mass, equal liquid level and tem., chemical compatibility, ...
- First two pairs of ADs have been successfully filled



Water pool prototype

[Chinese Phys. C33 \(2009\) 567-571](#)

- Purpose: to study pure water circulation, material compatibility, detector performance, ...
- Reach: Established a water circulation model for purification system design. Tyvek reflectivity 99%, water attenuation length $\sim 80\text{m}$ with the circulation system.
- MC modeling for light transport & light collection





circulation

8" PMT




2.8x1.2x1.3 m³ water tank



PMT signal with reflected photons



Water pool Installation



Installation in Hall 1 is finished

Dry water pool test

- Goals:
 - Check the hardware status
 - LED calibration system
 - Cover light tightness
 - Basic detector performances




RPC production and test


[Nucl. Instrum. Meth. A Volume 583, 278-284 \(2007\)](#)

[Chinese Physics C 2010 34 \(08\): 1116-1121](#)

- Almost all RPC bare chambers have been produced and tested.
- Efficiencies of all tested modules meet requirement ($> 95\%$).
- 176 modules have been transported to Daya Bay.



module ϵ vs. HV



RPC module test system



RPC installation

RPC supporting structure



Install modules




Gas system




Fully installed RPC



Hall 1 detector installation




in water



Clear demonstration of the water shielding effect.

Hall 1 detector installation

Water filling completed



Water pool covered



Hall 1 installation was finished and started taking data on Aug. 15!



Covered by RPC



Status of Ling Ao and Far Hall

Ling Ao Hall



Being installed

Far Hall




Almost done with installing the infrastructure





Offline analysis and hall 1 detector performances

Offline data processing




Real-time data monitoring




Detector performance(1)

Am-C Source at the center of AD

Neutron-capture energy spectrum





Neutron capture time



Detector performance(2)

- Hall 1 Water Cherenkov detectors PMT single rate





PMT single rate requirement <50 kHz:

- Observed rate is less than our requirements.

Detector performance(3)

Hall 1 Muon rate




Detector performance(4)

Hall 1 RPC



Hit map

Telescope modules



No dead strip/channel

Telescope modules



Summary and prospective

- Hall 1 started taking data since Aug 2011
- Hall 2 being installed
- Hall 3 almost done with installing the infrastructure
- Full experiment will start running in summer 2012!

